GLASS FLOORING SYSTEMS INC

6 Aaron Way, Sparta, NJ 07871 O - 862-701-5320
www.glassflooringsystems.com

Proposal # 16906 Rev A
Date: 1/14/25
Project Name: 464 Greenwich St
Project Address: 464 Greenwich St. New York, NY
Architect: Ernst Architect, PLLC
Contact: Zach Mathes
Phone: 862-305-0020
Email: zach@conklinglass.com
Quoted By: Frank Cortes

Thank you for your interest in Glass Flooring Systems. The following quote is for (1 Qty.) 58" x 58" Fully Assembled/Factory Glazed ICC approved Series 2000 SkyFloor® ultra high performance walkable skylight. This is a complete system which consists of our proprietary structural, thermally broken, pedestal perimeter framing with integrated gutter and weep system, setting gasket and one (1) structural walkable glass panel with tested anti-slip texture. The system will arrive fully assembled (welded) and factory glazed with the walkable glass panel bonded to the frame with Dow Corning 995 structural silicone. ***Glass panel is to endure Heat Soak Testing****. The make up of the glass panel is listed below. Please review and let us know if you have any questions or require additional information.*

Once you receive your SkyFloor® system all that is required for installation are three simple steps.

1. *Set assembled SkyFloor® system at prepared opening.*
2. *Secure assembled SkyFloor® system at prepared opening.*
3. *Complete field waterproofing.*

Glass Flooring Systems to supply as follows:

Unit	Drawing	Drawing Date	Location	Exposed Frame Dimension (inches)			Description
A	A-103.00 & A-500.00	9/16/24	Roof	58	x	58	(1 Qty.) 58" x 58" Fully Assembled/Factory Glazed ICC approved Series 2000 SkyFloor® ultra high performance walkable skylight

Glazing

Glass Make-up

10mm top layer – low iron tempered tested anti-slip texture. Final texture TBD. – ***Heat Soak Testing***
1.52mm interlayer – DG Structural
10mm middle layer – low iron tempered – ***Heat Soak Testing***
1.52mm interlayer – DG Structural
10mm bottom layer – low iron tempered with back painted border. – ***Heat Soak Testing***
20mm air spacer
4mm tempered Sun T
.76mm interlayer DG Structural
6mm low iron tempered

Frame Finish

Standard frame colors are painted PPG Coraflon black or white. Custom colors and finishes are available upon request - at an additional cost.

Frame Type

6063-T6 extruded aluminum, thermally broken, pedestal perimeter framing with integrated gutter & weep system and setting gaskets. System to arrive fully assembled (welded) and factory glazed.

Lead- time

Lead time 14 - 16 weeks after approved shop drawings but can vary depending on market conditions. See our terms and conditions for more information.

Shop drawings

Shop drawings will be completed 1 - 2 weeks from approved contract of sale and receipt of contractor's purchase order with deposit.

Base Pricing

Unit A	(1 Qty.) 58" x 58" Fully Assembled/Factory Glazed ICC approved Series 2000 SkyFloor® ultra high performance walkable skylight	$	10,106.92
Subtotal		$	10,106.92
NJ Sales Tax (6.625%)		$	669.58
Total		$	10,776.51

Anti-Slip surface texture is included in base price. *See our Terms and Conditions #20 for the texture options included in the base price. The Seeded Organic™ and NanoDot™ textures are available - at an additional cost listed below.*

Add - Seeded Organic™ anti-slip texture (Optional)

Unit A Add $ 1,195.62 Initial here _____ if you approve additional charge for our Seeded Organic™ texture.

Due to the production processes required in the manufacture of our (Kiln / Cast) Seeded Organic® anti-slip texture, the product may develop some imperfections such as some slight distortion or small bubbles within the make-up of the laminated assembly. These will not affect the structural integrity of the glass panel nor shall they be considered a defect.

Add - NanoDot™ anti-slip texture (Optional)

Unit A Add $ 1,394.89 Initial here _____ if you approve additional charge for our NanoDot™ texture.

Shipping and Crating *Add $ 747.50 Shipping to New York NY via dedicated truck*

Initial here _____ if you require shipping and crating and approve additional charge.

Customers are responsible for the unloading of the shipping/delivery vehicles. This responsibility includes, but is not limited to, arranging for labor and securing the necessary material handling equipment. For any questions regarding the specifics of your shipment's arrival, please contact us to ensure that you are fully prepared for the unloading process upon delivery.

Due to current market conditions - shipping costs are estimated and subject to change. Final cost will be determined upon shipment date

Engineering

Glass Flooring Systems Inc. offers a wide range of pre-engineered products. Engineering is not included in this proposal. Glass Flooring Systems Inc. can provide a complete engineering analysis & report including stamped shop drawings with glass specific calculations for each individual state. Each project has different engineering requirements. Please contact us if you require engineering. Glass Flooring Systems Inc. will provide pricing for engineering based on your requirements. It is the responsibility of the buyer to notify Glass Flooring Systems Inc. prior to ordering if the project requires an engineering report or stamped drawings.

Exclusions (from Base Price)

- *Shipping*
- *Installation*
- *Engineering*
- *Unloading labor and material handling equipment at jobsite*
- *Hoisting*
- *Fasteners or anchors of any kind not included*
- *Waterproofing connection to frames*
- *Preparation of openings*
- *Structural steel*
- *LED lighting and wiring*
- *Any other materials or services not specifically called out in this proposal*

Terms and Conditions

1. All payments are to be made in US currency.

2. 50% deposit due upon acceptance of this proposal and is required before production will commence. Balance due upon completion of production and prior to shipping. We will notify you 24 hours prior to shipment. Please use Certified or next day mail for balance.

3. NO sales or use tax of any description are included in the price unless specifically noted. All taxes related to the sale or delivery of these goods will be the sole responsibility of the buyer.

4. Shipping is FOB from Glass Flooring Systems facility in Sparta, NJ. All freight shipped with Glass Flooring Systems, Inc. carrier is insured. Quoted shipping is LTL shipping. For oversized freight and projects with time sensitive schedules GFS highly recommends shipping with either a dedicated truck or a secured bulkhead. GFS can provide costs for these options if requested. Unloading of delivery trucks is the sole responsibility of the customer. Customer to provide all required labor and or material handling equipment which may be needed to unload delivery vehicles.

5. Cancellation Costs: Customers who cancel any orders after items are manufactured will be charged full price for such items. Partially manufactured items will be charged at a pro-rated price. Administrative costs will be charged to customers on a project-by-project basis at Glass Flooring Systems discretion. 50% deposits are non-refundable.

6. Please note the industry standard tolerances for laminated glass is +1/4", – 1/8"

7. Quotes are valid for 30 days. After such times prices are subject to change without notice and a new quote will need to be provided.

8. Due to current market conditions final lead time for this project will be confirmed at the time of shop drawing approval. Any damage or breakage during the tempering and laminating processes could cause the lead time to be adjusted.

9. If shop drawings are not approved within 60 days of placing the order Glass Flooring Systems will have the right to review and revise pricing, if necessary, due to changes which may have occurred in market.

10.Glass Flooring Systems, Inc. is not responsible for any breakage/damage during installation.

11. It is agreed that Glass Flooring Systems, Inc. shall not be subject to liquidated damages, charges, back charges, penalties or liability whatsoever of any kind for delayed delivery due to strikes, slow-downs, floods, fires, accidents, contingencies of transportation, embargoes, inability to obtain raw materials, or any other cause beyond the control of Glass Flooring Systems, Inc.

12. The products included in this price quote are specified and approved by the customer, who assumes full responsibility for any errors or omissions in specifying or ordering same. Glass Flooring Systems Inc. assumes full responsibility for the accuracy of the shop drawings prepared by Glass Flooring Systems, Inc. however Customer assumes full responsibility for the error and omissions in the data supplied to Glass Flooring Systems, Inc. from which Glass Flooring Systems, Inc. prepares shop drawings.

13. Acceptance of this proposal shall be acceptance of all terms and conditions recited herein, which shall supersede any conflicting terms in any other contract document. Agreement of this quote and these terms shall be evidenced by Customer's signature heron by permitting Glass Flooring Systems, Inc. to commence work for this order.

14. Should Glass Flooring Systems, Inc. be required to store finished material at Customer's request, Customer agrees to reimburse Glass Flooring Systems, Inc. for all storage fees incurred by Glass Flooring Systems, Inc. and pay for the material being stored in full within Glass Flooring Systems, Inc. terms.

15. Glass Flooring Systems, Inc. will manufacture from approved shop drawings only. The Customer is responsible to ensure what is incorporated into the shop drawings is in acceptance with the contract documents, plans and specifications, all applicable local laws and regulations, building codes and any federal, state, county and municipal codes. The structural integrity of the opening in which Glass Flooring Systems, Inc. products will sit is the responsibility of our customer in accordance with design requirements as well as the product's suitability for this project.

16. When you receive your order, please inspect your entire order and notify Glass Flooring Systems, Inc. within 1 business day after receipt regarding any damages or questions and concerns related to the order. Unless so notified, Glass Flooring Systems, Inc. assumes no responsibility for the replacement of damaged glass or any labor cost associated with replacement.

17. Terms of this agreement and the enforcement of same will be governed by the laws of the state of New Jersey.

18. Any action arising out of this contract must be commenced in the New Jersey Supreme Court in the county of Sussex. By signing this agreement, Purchaser is consenting to the jurisdiction of the New Jersey Supreme Court in the County of Sussex and in any action arising out of this contract Purchaser will not be able to object that this court does not have jurisdiction over Purchaser.

19. If the seller brings an action against Purchaser to enforce this agreement or collect payment, Seller will be entitled to reasonable attorney's fees and costs associated with such action.

20. The following anti-slip textures are included in the base price. Bel Air T, Gramercy T, Greenwich T, Hudson T, Soho T, Tribeca T, Bel Air S, Brentwood S, Georgetown S, Greenwich S, Hudson S, Madison S, Park S, Soho S, Tahoe S, Williamsburg S, Hudson X and Yorlux. Add 4-6 weeks to your quoted lead time and additional costs are to be determined at shop drawing phase when jumbo anti-slip textures are required.

Sign and date below to accept the terms of this quote.

Accepted _____ *Date* _____

SKYFLOOR® walkable skylights

NFRC National Fenestration Rating Council®

Member of The American Institute of Architects

ICC ES